NGU Rapport 93.065

IMPPROF

Magnetic and Gravity Profile

Database



Postboks 3006 - Lade 7002 TRONDHEIM Tlf. (07) 90 40 11 Telefax (07) 92 16 20

# **REPORT**


		<del>{</del>			
Report no. 93.065		ISSN 0800-3416		Grading: Åpen	
Title: IMPPROF - Magnetic and Gravity Profile Database					
Author: T.H. Torsvik & O. Olesen		Client: NGU			
County:		Commune:			
Map-sheet name (M=1:250.000)		Map-sheet no. and name (M=1:50.000)			
Deposit name and grid-reference:		Numl	ber of pages: 39	Price: kr 60,-	
	<del></del>		Map	enclosures:	
Fieldwork carried out:	Date of	report:	Proje	ct no.:	Person responsible:
12.05.93		24	.0123.01	Jan S. Roung	
IMPPROF is an interactive database system for storage and manipulation of magnetic and gravity profiles. Profiles can be displayed together with gridded image files and/or geographic vector data. The system principally aims to extract and manipulate profiles interactively on the screen. A selected profile can subsequently be exported for pseudo-3D forward modelling and/or interactively subjected to magnetic or gravity inversion.				ulation of magnetic and mage files and/or geographic e profiles interactively on the	
Keywords:		Magnet	ometi	·i	
Database		Gravii	metri		
Tolkning		Geofy	ysikk		Brukerdokumentasjon

CONTENT	PAGE
<del></del>	<del></del>

1.	INTROD	UCTION3
		RDWARE REQUIREMENTS4 PPROF FILE TYPES (MAIN)5
2.	INSTAL	LATION OF IMPPROF6
3.	DESCRI	PTION OF IMPPROF7
	3.1	OPEN DATABASE9
	3.2	OPEN GRID FILE10
	3.2.1	CREATE A GRID FILE USING GDB212
	3.3	OPEN UTM FILE
	3.4	IMP5 MODELLING14
	3.5	MAGNETIC INVERSION
	3.6	GRAVITY INVERSION
	3.7	DRAW SURVEY21
	3.7.1	CRIMG.(CREATE IMAGE)25
	3.7.2	LASER
	3.8	IMPORT DATA28
	3.9	SELECT PROFILE
	3.10	DEPTH ANALYSIS32
	3.11	SET SYSTEM
4.	REFERE	NCES37
ΆPI	PENDIX	1 SETTING AUTOEXEC.BAT & CONFIG.SYS38
		2 EDITOR USE IN IMPPROF

IMPPROF is an interactive database system for storage and manipulation of magnetic and gravity profiles. Profiles can be displayed together with gridded image files created with GDB2 (Smethurst 1992) and/or geographic vector data generated with IMPATLAS (Torsvik 1992a).

The system principally aims to extract and manipulate profiles interactively on the screen. A selected profile can subsequently be exported to IMP5 (Torsvik 1992c) for pseudo-3D forward modelling and/or interactively subjected to magnetic or gravity inversion utilizing the programs PDEPTH (Torsvik & Olesen 1992) or GDEPTH (Torsvik & Fichler, 1993).



## 1.1 HARDWARE REQUIREMENTS

# System requirement:

- IBM AT or compatible (80286/386/486) computer
- Mathematical co-processor (80287/387/487)
- VGA (colour) graphics card
- Microsoft compatible mouse (3 button)

# Graphical Output Devices:

- HP Laser/Deskjet compatible printer,

  HP Deskjet 500C (colour) the optimal choice, or
- almost any output devices via the use of HALO Graphics Kernel System. This, however, needs a separate software licence (Copyright Media Cybernetics, Inc., USA) and the use of the program IMPRINT (Torsvik 1992b).

## 1.2 IMPPROF FILE TYPES (MAIN)

## Programs:

IMPPROF.EXE - Main database program

IMPORTP.EXE - Import Program for ASCII files

PDEPTH.BAT - Magnetic inversion control

GDEPTH.BAT - Gravity inversion control

## Files:

\*.PID - Profile Index File

\*.PDB - Profile Database File

\*.DAT - Profile Info File

\*.REP - Profile Report File

\*.INT/.RED/.BLU/.GRN - Profile Image Files

\*.XSP - Profile help file

\*.YSP - Profile help file

\*.GDI - Grid Info File

\*.UTM - Geographic contour (coastline) file

IMPPROF.SYS - IMPPROF System file

IMPORTP.SYS - IMPORT system file

\*.PTZ - Depth analysis file

Program and files used with PDEPTH, GDEPTH, IMP5 or GDB2 are described seperately (Torsvik & Olesen 1992a; Torsvik & Fichler 1993; Torsvik 1992c; Smethurst 1992).

## 2. INSTALLATION OF IMPPROF

- Type A:INSTALL at the DOS system prompt.

  This will create a sub-directory named \MAGMOD\IMPPROF (if not already done) and copy all files to sub-directory MAGMOD\IMPPROF.
- Trim AUTOEXEC.BAT AND CONFIG.SYS as suggested in Appendix 1 in order to have the maximum memory available for the system.
- Add MAGMOD directory in the AUTOEXEC.BAT (unless previously done) file by typing PATH C:\MAGMOD (see Appendix 1)
- Install MOUSE driver (see CONFIG.SYS; Appendix 1)

## 3. DESCRIPTION OF IMPPROF

Type IMPPROF at the DOS system prompt or select sub-option IMPPROF in the IMP menu program. The program immediately searches for a configuration file named IMPPROF.SYS. If this file is not found on the \MAGMOD\IMPPROF directory, IMPPROF.SYS is automatically created, containing the default values listed in section 3.11.

After start-up the main menu is displayed (Fig. 1). An option in the menu may be selected through the use of the arrow keys, and executed by pressing <ENTER>.

FIGURE 1 Main menu IMPPROF

OPEN DATABASE IMP5 MODELLING	
	C DDAW CHDURV DEDTH ANALYCIC
	G DIGM DONVEL DELTH MINELDED
OPEN GRID FILE MAGN INVERSION	N IMPORT DATA SET SYSTEM
OPEN UTM FILE GRAV INVERSION	N SELECT PROFILE QUIT
	Info
PROFILE DBASE CURRENT PROFI	
LOFGRAV 0	LOFGRA1R.GDI LOFOTEN.UTM
PROFILES STATIONS	MEMORY LINES
1155 0	347008 0


The main menu has the following options:

OPTION	EFFECT
OPEN DATABASE OPEN GRID FILE OPEN UTM FILE IMP5 MODELLING MAGN INVERSION GRAV INVERSION DRAW SURVEY IMPORT DATA SELECT PROFILE DEPTH ANALYSIS SET SYSTEM QUIT	SELECT PROFILE DATABASE SELECT GRID FILE SELECT UTM FILE (COASTLINE FILE) EXPORT A PROFILE TO IMP5 FORMAT MAGNETIC INVERSION (RUN PDEPTH) GRAVITY INVERSION (RUN GDEPTH) DISPLAY PROFILE DATABASE ON SCREEN IMPORT PROFILES FROM AN ASCII FILE SELECT A PROFILE FROM DATABASE CREATE A DEPTH TO BASEMENT FILE SET SYSTEM CONFIGURATION END PROGRAM

The information box below the main menu contains information regarding PROFILE DBASE FILE, NUMBER OF PROFILES, CURRENT (SELECTED) PROFILE, NUMBER OF PROFILE STATIONS, NAME OF GRID-FILE AND NAME OF UTM FILE.

The current directory is automatically sorted and the available profile databases (index files with extension .PID; actual database file has extension .PDB) are displayed (Fig. 2). Use cursor arrows (use <PGUP> & PGDN> keys to change directory 'page') to select the appropriate file followed by <ENTER>. Use <ESC> to leave this option without selecting a file.

FIGURE 2 Sorted list of profile data-base files using option 'OPEN DATABASE'



## 3.2 OPEN GRID FILE

The directory is sorted and available GRID~FILES (index/info files with extension .GDI) are displayed. Use cursor arrows (use <PGUP> & PGDN> keys to change directory 'page') to select the appropriate file followed by <ENTER>. Use <ESC> to leave this option without selecting a file.

NOTE: Assure that grid-files (extension \*.GDI) are in the local directory, i.e. \MAGMOD\IMPPROF.

The grid can be displayed as an underlay for the profiles in option 'DRAW SURVEY'.

After selecting a grid-file (created from GDB2; Smethurst 1992), grid-file information is displayed on the screen (Fig. 3).

FIGURE 3 Display of grid-file information

```
Grid Data Name :\gdb\gdata\lofgralr.BIN
StartX : 50000
StartY : 7950000
UTM Units : 4
UTM Zone : 33
Grid Col. Spacing : 1000
Grid Row Spacing : 1000
Number of rows : 551
Number of columns : 801
Multiplication Fac: 48.7223
Offset :-313.74
Zmax : 18763
Zmin : 13243
ZDefault :-32768
```

## PROCEDURE (Cf. Smethurst 1992 for details):

- 1. Start GDB2 from the IMP menu
- 3. VIEW : Read the image file and mark a sub-region from the grid
- 4. EXPORT : Grid

  Confirm export to a new GDB database entry (type y)

  Enter new database GRID name

  Confirm to make a subset (type y)
- 5. SELECT : Grid

  Select the newly created GRID file ——
- 6. EXPORT : Grid 
  Negate export to a new GDB database entry (Type  $\underline{n}$ ) 
  Confirm creation of an information file (Type  $\underline{y}$ )

This procedure creates a binary GRID file located in sub-directory \GDB\EXPORT. The information file will be stored in the local directory from where GDB2 was started. For example, if you run GDB2 from the IMP menu program, the information file will be stored in the \MAGMOD\ directory with file extension .GDI. You must copy this file to \MAGMOD\IMPPROF directory (COPY c:\magmod\\*.gdi c:\magmod\impprof).

This option loads a contour data-file, i.e. a UTM file with paired X (EAST) and Y (NORTH) co-ordinates (Standard ASCII file with X and Y co-ordinates; -9999.0 -9999.0 indicate 'pen-up'). A UTM file can be generated with the program IMPATLAS (cf. Torsvik 1992a) for Norwegian data or during IMPORT (see later).

Upon entering this option the current directory is sorted. Use cursor arrows to select the appropriate profile file followed by <ENTER>. Use <ESC> to leave this option without selecting a file.

Make sure that the UTM file is generated with 10 meters precision, i.e. using factor 100 in IMPATLAS (Torsvik 1992a). Also assure that the UTM-file is generated with the same UTM-ZONE (30-37) as the profile-data-base and/or grid-files.

This option is used to export selected profiles to IMP5 dataformat. Number of profile stations, average data-spacing, total
distance and profile direction is displayed when entering this
mode. IMP5 format profiles are created with file-extension \*.OUT
and stored in directory \MAGMOD\. The operator is prompted to
execute IMP5 or not (y or n).

## NOTE

IMP5 only handles profiles with a maximum of 300 data stations. For longer profiles this problem can be overcome by <u>increasing</u> the 'Profile sampling rate (profile mode)' in option 'SET SYSTEM' <u>before you select a profile</u> in order to decrease the number of stations.

This sub-option allows IMPPROF to interface with PDEPTH (Torsvik & Olesen 1992a), a program to calculate depth to magnetic basement.

This option can only be used for <u>equally spaced</u> data-points, hence spline fitting is automatically performed in order to create equally spaced stations. The maximum number of points is 1024; the operator is prompted for number of points, but can always use the displayed default value. If the default-value is above 1024, the value is automatically set to 1024.

The operator is further prompted for autocorrelation window length/length of the adaptive window (in number of data-points). 15-20 is a good starting value for profiles with approximately 100 data-points. An upper value (maximum) is indicated dependent on the depth of maximum interest (listed for 2, 5 and 10 km). See Torsvik & Olesen (1992a) for detailed operation of PDEPTH. Finally, the operator can enter flight height (for magnetic data) in order to correct the calculated inversion depths (Fig. 4). An example of depth estimates is shown in fig. 5.

FIGURE 4 'MAGN INVERSION' option


Profile Stations 330 Calculated Dataspacing : Calculated Distance : 0.1600 km (Min 0.0793 Max 52.6242 km 0.1753) Calculated Direction 138.1982

Number of points (MAX 1024 ):330

Maximum Window Lengths : 25 (2km) 62 (5km) Autocorrelation Window Length:30 125 (10km)

Fligth Altitude (in km) :0.5

FIGURE 5 Example of magnetic inversion



This option (Fig. 6) initiate gravity inversion and calculates basement surface depths (Cf. GDEPTH; Torsvik & Fichler 1993). Maximum number of data-points is 105 and data must be equally spaced, hence spline fitting is a necessity (automatic). Parameters which affect the gravity inversion solutions are as follows:

# 1. Number of iterations (100=default):

The gravity inversion routine uses an iteration scheme which employs Markquardt's (1963) optimization. Iteration will always terminate when the Markquardt's damping factor become large, i.e. >15 (cf. Murthy & Rao, 1989). The operator, however, can terminate iteration interactively at any stage by setting a maximum value of iterations.

## 2. Damping Factor Lambda (0.5=default):

The Markquardt's damping factor (see above) controls termination of the iterative inversion process.

## 3. Lowpass Filter Value (odd number; 5=default):

In order to 'smooth' oscillating depth estimates a lowpass filter (moving average) has been implemented. Only <u>odd</u> numbers should be entered (1,3,5,7 etc.).

## 4. Profile Extension (y or n; n=default):

The program automatically subtracts a regional trend (if not This implicate that inversion of asymmetric already removed). gravity profiles, e.g. associated with intra-basement faulting, results in erroneous depth estimates. In such cases it is necessary to 'extend' the original profile. The profile is extended 50% and the extended anomaly values are linearly interpolated between the <u>end</u> profile value and corresponding to the start value. Depth values will now be correct, but it is obvious that depth estimates along the extended part of the profile should not be used.

## 5. Depth to interface (in km):

The gravity inversion procedure initially assumes a flat basement topography, i.e. the density surface between sediments and basement, at a specific depth which must be defined by the operator. This depth will represent the depth to basement at the starting point of the profile. The choice of minimum and maximum depth's (see below) dictate inversion convergence.

# 6. Minimum depth to interface (in km):

Set minimum depth to interface (see point 5).

## 7. Maximum depth to interface (in km):

Set maximum depth to interface (see point 5).

## 8. Density contrast across interface (in 1000kg/m³):

Set density contrast across interface in 1000kg/m³ (= g/cm³; e.g. 0.3)

## 9. Station interval (in Km):

All data-points must be equally spaced (maximum 104) and station interval is given in kilometre. The listed station interval is an average based on reel data. Ignore this entry since spline fitting should be performed (see below).

The operator select number of points (equally spaced distances is then automatically calculated based on maximum number of points). The default value can always be used; number of points above 104 will be set to 104.

# FIGURE 6 Option 'GRAV INVERSION'

```
Number of iterations (100=default) :5

Damping Factor Lamda (0.5=default) :0.5

Lowpass Filter (moving average;1,3,5,7 or 9) :5

Profile extension (Y or N) :n

Depth to Interface (in Km) :5


Minimum depth to interface (in Km) :0

Maximum depth to interface (in Km) :10

Density contrast across interface (in 1000kg/CM) :0.3
```


```
Number of points (MAXIMUM 104):110
```

FIGURE 7 Example of gravity inversion.



After the operator has selected a profile database (option 'OPEN DATABASE' all profile lines (a Survey) are displayed (Fig. 8) on the screen upon accessing this option. The start-point for each profile is indicated as a <u>red</u> dot. The details in the profile lines are drawn according to the 'Profile sampling rate (survey mode)' in option 'SET SYSTEM'. The map scale is displayed in the upper left corner, whereas X(east) and Y(north) co-ordinate for the position of the mouse arrow is indicated in the bottom left corner.

FIGURE 8 Option 'DRAW SURVEY'



Sub-options (type  $\underline{h}$  = HELP for screen display) are as follows:

OPTION	EFFECT	
LEFT BUTTON	SELECT A PROFILE	
	-MOVE ARROW TO A PROFILE AND CLICK THE LEFT BUTTON	
	-THE SELECTED PROFILE NUMBER IS DISPLAYED IN THE BOTTOM RIGHT CORNER OF THE SCREEN ALONG WITH THE NUMBER OF STATIONS/VALUE OF POINT1 -THE ACTUAL PROFILE IS HIGHLIGHTED ON THE SCREEN AND DISPLAYED IN THE TOP RIGHT CORNER OF THE SCREEN (Fig. 9) -FOR GRAVITY DATA FREE AIR/BOUGUER ANOMALIES WILL BE DISPLAYED IN YELLOW/WHITE RESPECTIVELY (SEE SET SYSTEM)	
MIDDLE BUTTON mouse	SELECT A POINT WITHIN A PROFILE -SELECT A PROFILE (SEE ABOVE) -MOVE ARROW TO A SELECTED POINT WITHIN THE PROFILE AND CLICK THE MIDDLE BOTTOM -ACTUAL DATA VALUE FOR THE POINT WILL BE DISPLAYED IN THE BOTTOM RIGHT CORNER	
RIGHT BUTTON mouse	-MOVE ARROW TO DESIRED ZOOM-CENTRE AND	
	CLICK RIGHT BUTTON -PROFILES WILL BE REDRAWN CENTRED AROUND THE NEW ZOOM-CENTRE	
	-STOP PROFILE DRAWING AT ANY STAGE BY PRESSING THE 'A' (ABORT) KEY	
ARROW KEYS	SCROLL MAP UP/DOWN OR SIDEWAYS	
PG UP / PG DN	EXPAND / DECREASE SCALE BY FACTOR 2	
1-SOL/ 2-EOL	DEFINE A NEW START AND/OR END OF A PROFILE -SELECT PROFILE AND A POINT WITHIN THE PROFILE (SEE ABOVE) -TYPE 1 TO INDICATE START OF LINE (SOL) -SELECT A SECOND POINT WITHIN THE PROFILE -TYPE 2 TO INDICATE END OF LINE (EOL)	
CrIMG	CREATE A DEFAULT IMAGE FOR THE SURVEY -TYPE $\underline{C}$ (SEE LATER DESCRIPTION)	

OPTION	EFFECT		
PROF	DRAW PROFILES -TYPE P (ABORT DRAWING BY PRESSING THE 'A' KEY)		
GRID	DRAW A GRID DEFINED IN OPTION 'OPEN GRID' -TYPE G (ABORT DRAWING BY PRESSING THE 'A' KEY)		
МАР	DRAW A UTM-FILE SET IN OPTION 'OPEN UTM' -TYPE M (ABORT DRAWING BY PRESSING THE 'A' KEY)		
INVERT	INVERT PROFILE CO-ORDINATES -TYPE I -START WILL BECOME END AND VISA VERSA		
LASER	COPY IMAGE TO A HP-LASER/DESKJET PRINTER -TYPE <u>L</u>		
SCALE	SET MAPSCALE -TYPE S FOLLOWS BY SCALE		
UTMG	DEFINE UTM GRID SPACING -TYPE U FOLLOWED BY SPACING IN KM		
QUIT	RETURN TO MAIN MENU -TYPE Q		

# NOTE:

When a profile has been selected in option 'DRAW SURVEY' then this profile can subsequently be exported to IMP5 format or processed using the magnetic or gravity inversion routines available from the main menu.

FIGURE 9 Example of selecting a profile





FIGURE 10 Example of change of zoom-center and map expansion



Whenever a profile data-base has been created (using option 'IMPORT DATA') it is convenient to create an image file which is displayed whenever option 'DRAW SURVEY' is engaged. This will speed up the system considerable.

The procedure to construct an image file is as follows:

(1)

- Select a profile database with option 'OPEN DATABASE'
- Select a grid (if available) with option 'OPEN GRID FILE'
- Select a UTM file (if available) with option 'OPEN UTM FILE'
  Assure that all files are produced for the same UTM zone

(2)

- Select option 'DRAW SURVEY'
- Zoom, Scale and display Profiles, Grid and/or Utm-file on the screen
- The screen can be saved to an image file at any stage by pressing the <u>c</u> key. This produces four image files with the names \*.INT,\*.RED,\*.GRN & \*.BLU (\*='Profile Database Name') plus an image information file named <Profile Database Name>.DAT.

## NOTE 1:

The default image file associated with a particular Profile Database can be changed at any time by pressing the  $\underline{c}$  key.

## NOTE 2:

Image files can subsequently be copied to a printer with the aid of the program IMPPRINT (Torsvik 1992b) or directly to an HP LASER/DESKJET printer by pressing the  $\underline{1}$  (=laser) key.

#### NOTE 3:


When option 'DRAW SURVEY' is used for the first time, the default image is loaded (if created). Subsequent use of option 'DRAW SURVEY' loads an image which resemblance any changes to the default image.

This option provides a hardcopy of the screen to a <u>HP LASER/DESKJET</u> compatible printer (will not work if a POST-SCRIPT cartridge is installed). For any other output-device make sure that you first save the screen using the option 'CrIMG' (see previous section). Images can subsequently be copied to a printer with the program IMPPRINT (Torsvik 1992b).

This option converts profile data from ASCII format to IMPPROF profile database format (creates a new set of binary random access files). The input ASCII file <u>must</u> have the following format (cf. EXAMPLE.XYZ located in sub-directory \MAGMOD\IMPPROF):

PROFILE-NAME SHOT-POINT X(EAST) Y(NORTH) Z(W-DEPTH) VALUE A16 I6 F9.1 F9.1 F7.1 F7.1 Note that Z(depth or height) should always be in meter units.

The import option produces two binary random access files and two ASCII information/report files (see below). The report file contain the actual profile-name which relates to the actual profile-number used in IMPPROF. This file can be copied to a printer, e.g. using the DOS command COPY <NAME>.REP LPT1:



## NOTE:

During operation of IMPPROF two more files are created (named <NAME>.XSP & <NAME>.YSP) when the profile database is accessed for the first time. If any of these two files or the <NAME>.DAT file is deleted the system will crash.

Whenever importing and converting an ASCII file to IMPPROF format, the operator is prompted for the following information (Fig. 11):

- (1) Input File Name
- (2) Output File Name (use no file extension)
- (3) UTM factor for input file (1=km,10=100m,100=10m & 1000=meter units)
- (4) UTM zone for input file
- (5) IMPATLAS directory (e.g. \atlas\)

## Create a UTM file:

When importing data the program determines the geographic area covered by all the profiles and this information is stored in file <NAME>.DAT (never delete this file). This information can subsequently be used to construct a UTM map for the region. UTM maps are always created with 10 meter units.

After converting all profiles the operator can produce a UTM map (Fig. 12), but it is of ultimate importance that the UTM map is produced in the same UTM zone as the original profile data.

The import option is ended by displaying a status report on newly created files.

# FIGURE 11 Option 'IMPORT DATA'; Import Menu Options

PROGRAM IMPORTP - IMPORT ASCII PROFILES TO IMPPROF FORMAT THT/NGU 1992

INPUT FILE NAME :lofgra2f.xyz

OUTPUT FILE NAME (NO EXTENSION) :DUMMY

UTM FACTOR (1=km,10,100,1000=m) :100

UTM ZONE (31,32,33,34....) :33

IMPATLAS DIRECTORY (e.g. \atlas\):\MAGMOD\KYST\

START IMPORTING (y/n) :n

## FIGURE 12 Option 'IMPORT DATA'; Create a UTM map

Create a UTM map file from Norwegian coastline file: KYST.BIN MinLat 70.040 MinLong 17.126 MaxLat 71.818 MaxLong 25.918

UTM Zone :33 Start Exporting (y/n) :y At Rec 13000

STATUS REPORT: FILES CREATED: DUMMY.PID (BINARY INDEX FILE) (BINARY DATA DUMMY.PDB FILE) (ASCII REPORT FILE) DUMMY.REP MIN/MAX FILE) DUMMY.DAT (ASCII DUMMY.UTM (ASCII UTM FILE)

Record Size is 81254 for FILE KYST.BIN Press A to Abort

The program is principally designed to select profiles graphically, but this option allows the operator to select a profile by entering the appropriate profile number (within the profile database, profiles are organized and identified by numbers <1 to N> and not their original profile names). The selected profile is displayed on the screen and the operator may invert (turn) the profile if necessary by typing y. It is also possible to export the selected profile to an ASCII file (output format is <u>Distance along profile</u> and <u>Z-value</u>; free format; file name = <Profile Number>.EXP) which can later be used for other purposes (e.g. own-built inversion routines etc.)

Note for gravity data that <u>free air anomalies</u> are drawn in yellow and <u>Bouguer</u> corrected anomalies in white (if bathometry data are available and 'Bouguer correction' is set to <u>y</u> (yes) in option 'SET SYSTEM'. In the latter case, the Bouguer corrected data is used for gravity inversion.

# Depth Save Files in PDEPTH/GDEPTH:

Whenever accessing the magnetic and gravity inversion programs (PDEPTH and GDEPTH) from IMPPROF, the operator can now interactively select depths in option 'VIEW' and store these depthestimates in a file. The file-name is set in option 'CONFIGURE' ('Name of Depth Save File') and they are automatically given file-extension .PTZ. This file (free format ASCII file) contain the following information:

- -Profile Database name/Profile number
- -Inverted (-1) or regular profile (1)
- -Distance along profile
- -Actual Depth

For a particular project the operator can use the same file-name since depths from consecutive profile depth estimates are 'appended' to the existing data.

# How to select depths interactively:

- -Select a profile in IMPPROF
- -Select option 'MAGN INVERSION' or 'GRAV INVERSION' (IMPPROF)
- -Select option 'VIEW' in PDEPTH or GDEPTH
- -Move mouse cursor to a selected depth (distance=X and depth=D is displayed in the lower left corner) and click any mouse buttom. This will save ('append') the actual depth value and distance in the file defined in option 'CONFIGURE' (in PDEPTH/GDEPTH).

## How to create the final depth file:

- -Select the appropriate profile database with option 'OPEN DATABASE' in IMPPROF
- -Select option 'DEPTH ANALYSIS'
- -Select input depth file (with extensions .PTZ)
- -Enter the file-name of the final output depth file

A new depth-file with X,Y and DEPTH (all in km units) will now be created. This file can later be used to produce a depth grid- or contour-map with any commercial software or by hand-drawing.

## 3.11 SET SYSTEM

This option (Fig. 13) permits the adjustment of parameters which control program output and performance.

A configuration file named IMPPROF.SYS (free format ASCHI file) contains names of the variables which are adjusted using 'SET SYSTEM'. Whenever a parameter is changed, the file IMPPROF.SYS is automatically updated, thus recording the adjustment even after IMPPROF is terminated.

The following parameters can be changed/updated:

PARAMETER	VALUE
PROFILE SAMPLING RATE (PROFILE EXTRACT) (Initial value=1; read all data points) -This sampling rate is used whenever a selected profile is read from the disk	1 to N
PROFILE SAMPLING RATE (SURVEY DISPLAY) (Initial value=100) -This sampling rate is used to generate an overview off all profiles in a the database	1 to N
AUTOCORRELATION WINDOW LENGTH (Initial value=40) -Value is used for magnetic inversion Cf. Torsvik & Olesen 1992a	1 to N/2
BOUGUER CORRECTION (Initial value=y)	y or n
BOUGUER PLATE DENSITY (1000kg/m³) (Initial value=2.67)	any value

PARAMETER	VALUE
-This value is used for calculating bouguer gravity anomalies from free air gravity anomalies	
<pre>NUMBER OF ITERATIONS (Initial value = 100) -Value controls termination of gravity inversion if no convergence; should be set at a high value</pre>	1 to 100
DAMPING FACTOR LAMBDA	0 to 15
LOWPASS FILTER (Initial value=5)	1,3,5 or 7
PROFILE EXTENSION (Initial value=n)	y or n
DEPTH TO INTERFACE (in km) (Initial value=5)	any number
STATION INTERVAL (in Km)	
FREE	
PRINTER PORT (Initial value=lpt1:)	com1:,com2,lpt1: or lpt2:
BAUDRATE (for com1: or com2:) (Initial value=9600)	110,300,600,1200 ,2400,4800 or 9600
PARITY (for com1: or com2:) (Initial value=n)	<u>n</u> o, <u>e</u> ven or <u>o</u> dd
DATABITS (for com1: or com2:) (Initial value=8)	7 or 8
STOPBIT (for com1: or com2:) (Initial value=1)	1 or 2
FREE	
PLOT SIZE LASER DUMP (Initial value=3)	1(small) 2, 3 or 4 (large)

Cf. Torsvik & Olesen 1992a and Torsvik & Fichler (1993) concerning parameters controlling magnetic and gravity inversions.

FIGURE 13 Option 'SET SYSTEM'

	SET S	YSTEM===	<del></del>
1	Profile sampling rate (pr	ofile mode)	:1
	Profile sampling rate (survey mode)		:100
MAGN INV			:30
GRAVITY	Bouguer Correction (y/n)		<b>:</b> y
GRAVITY	Bouguer Plate Density (GM	(/CC)	:2.67
11	Number of iterations		<b>:</b> 5
31	Damping Factor Lamda		:0.5
	Lowpass Filter (moving av		· ·
	Profile Extension (y or n	:n	
	Depth to Interface (in km	:5	
	Minimum depth to Interfac	:0	
	Maximum depth to Interface (in Km)		
GRAV INV	Density Contrast (in 1000kg/CM)		
N .	Station Interval (in Km)		:.5750551
TAGED	Designation Designation (P)	/3	.7
LASER	Printer Port LIST/F1		
LASER	Baudrate Parity	(110 to 9600 )	
"	Databits	(n,o or e ) (8 or 7 )	:n
LASER	Stopbits	(1 or 2 )	:8 :1
TUSTIK	prophites	(1012)	• ±
LASER	Plot Size LASER-DUMP	(1 to 4) )	:3

#### 4 REFERENCES

- Marquardt, D.W., 1963. An algorithm for least-squares-estimation of non-linear parameters. J. Soc. Industr. Appl. Mathematics, 11, 2, 431-441.
- Murthy, I.V.R. & Rao, S.J., 1989. Short Note:

  A Fortran 77 program for inverting gravity anomalies of twodimentional basement structures. Computing & Geosciences, 15,
  7, 1149-1156.
- Smethurst, M.A., 1992. GDB: Et PC database program for data som er systematisk ordnet i et rutemønster, og profiler gjennom slike rutenett. NGU Report 92.328.
- Torsvik, T.H., 1992a. IMPATLAS Geographic database and mapgenerating system. NGU Report 92.223.
- Torsvik, T.H., 1992b. IMPPRINT A Print-Driver Program.

  NGU Report 92.304.
- Torsvik, T.H., 1992c. IMP5 Interactive Modelling of Potential Field Data (Release 5). NGU Report 92.305.
- Torsvik, T.H. & Olesen, O., 1992a. PDEPTH Calculation of depth to magnetic basement from profile data. NGU Report 92.212.
- Torsvik, T.H. & Olesen, O., 1992b. IMPPET Petrophysical Database System. NGU Report 92.275.
- Torsvik, T.H. & Fichler, C., 1993. GDEPTH Gravity Inversion and calculation of basement depths. NGU Report 93.066

#### APPENDIX 1 SETTING AUTOEXEC.BAT & CONFIG.SYS IN MS-DOS 5

## Example of AUTOEXEC.BAT set-up with QEMM memory manager

```
@ECHO OFF
PROMPT $p$g
PATH C:\dos
SET COMSPEC=C:\DOS\COMMAND.COM
SET DOS16M=11
SET TEMP=C:\DOS
MODE CON CODEPAGE PREPARE=((865) C:\DOS\EGA.CPI)
MODE CON CODEPAGE SELECT=865
c:\qemm\loadhi /r:1 c:\dos\doskey.com
PATH C:\MAGMOD
c:\qemm\loadhi /r:2 c:\mouse\mouse.com
```

# Example of CONFIG.SYS set-up with QEMM memory manager

## APPENDIX 2 GENERAL EDITOR/INPUT FUNCTIONS IN IMPPROF

When entering a single data-entry or editing etc., the following general features are implemented:

Up/Dn arrows : Move up/down in input tables

Left/Right arrows: Move Left/Right within a single data-entry

<RETURN> : Move to next entry field or end a

single data entry routine

<ESC> : Escape/Quit input/edit mode

<INS> : Change from INSERT to REPLACE (overwrite)

mode or from REPLACE to INSERT mode.

(Defaults to REPLACE mode)